



## **2000 GALLON SEPTIC TANK**

## NOTES:

CONCRETE TO BE MIN. 4000 PSI AT 28 DAYS
AIR ENTRAINED 5 - 8%
DESIGN LOAD 300 PSF
BUTLY SEALANT ASTM C - 900 AT JOINT
TUF - TITE TS4PRO SEAL AT ALL PIPE CONNECTIONS



